FARRELL'S
SHRINKWRAP

SCOFFOLDING SETUP GUIDE
FOR FARRELL'S SHRINKWRAP

Please review this guide before our team arrives on site. It explains the conditions required so **Farrell's Shrinkwrap** can complete your project safely, efficiently and to a high standard.

ACCESS





- All areas that need to be shrinkwrapped must have fully boarded, clear and safe access including compliant handrails on every tartking lift
- Our installers must be able to reach every part of the sheeting area comfortably with both hands at the same time

WEATHER



- High winds-and heavy rain can delay or suspend shrink-wrap installation
- Work should not begin unless the forecast allows enough time for all installed sheets to be fully welded and heat-shrunk before the team leaves site
- Partially shrunk sheets can move in the wind and damage welds and sheeting

ELEVATIONS/ SHEETING RAILS

- Fix a horizontal sheeting rail to the outside of the scaffold at both the top and bottom of the area to be wrapped
- Where a horizontal join between sheets is needed (typically every six metres or every three lifts), install two horizantal sheeting rails approximately 20cm apart



A minimum pitch of 15° is required to allow excess water to drain board



Roof Sheeting rails must be installed beneath the perpendicular boards 20cm away from boards to be secure



Two hand rails, approximately 20cm apart need to be installed around the scaffolding



Two boards should be installed every two metres following the pitch



Any additional run of five boards every six metres laid at right angles to the pitch or in any location or a run of three boards should be installed around the perimeter of the roof, please leave the toe board off to ensure that the sheeting runs smoothly over the edge



Roof access should be via ladder and safety access gate, at the side of the roof. Where access is provided through there's a risk of lasks in the completed job

FARRELL'S
SHRINKWRAP

Please contact me for a free no obligation conversation about your requirements.
Call Conor on +353 85 771 3098 • info@farrellsshrinkwrap.com